

Scaling Offsite and Volumetric Modular: Evolving Systems and Strategies for Success

Credits: 1.0 AIA/CES HSW LUs, 1.0 PHD credit, 0.10 ICC credit

MASS TIMBER+SM
OFFSITE CONSTRUCTION CONFERENCE

PRODUCED BY



Forest Economic Advisors

Peter Rose

Peter Rose + Partners,
IDCUBED



**Todd
Beyreuther**
Earth Force Build



Justin Hersh
Reframe Systems





Scaling Offsite and Volumetric Modular

Todd Beyreuther PE

Head of Platform Development, Earth Force Build

Disclaimer: This presentation was developed by a third party and is not funded by WoodWorks or the Softwood Lumber Board.



Technoeconomics of **resources**

Strategic Intent: Connect natural environment offtakes with built environment offtakes






Photo credit: Jed Conklin




Technoeconomics of **stewardship**

Strategic Intent: Connect natural environment offtakes with built environment offtakes




Technoeconomics of **markets**

Strategic Intent: Connect natural environment offtakes with built environment offtakes




Technoeconomics of **community**


Strategic Intent: Connect natural environment offtakes with built environment offtakes




DF = Douglas-fir




WH = Western Hemlock



GF = Grand Fir




LP = Lodgepole Pine



PP = Ponderosa Pine

Technoeconomics of **species**

Strategic Intent: Connect natural environment offtakes with built environment offtakes



Western larch
Larix occidentalis
230 ft



Douglas-fir
Pseudotsuga menziesii
200 ft



Western hemlock
Tsuga heterophylla
165 ft




Ponderosa pine
Pinus ponderosa
165 ft



Lodgepole pine
Pinus contorta
100 ft

Technoeconomics of **species**


Strategic Intent: Connect natural environment offtakes with built environment offtakes



Technoeconomics of **restoration**



Strategic Intent: Connect natural environment offtakes with built environment offtakes

photo credit: Earth Force Technologies



Technoeconomics of **grading** and **sorting**

Strategic Intent: Connect natural environment offtakes with built environment offtakes



Technoeconomics of **milling**

Strategic Intent: Connect natural environment offtakes with built environment offtakes

DEVELOP 35mm and 30mm ELAM programs


Key Takeaway: BID projects are designed on a 35mm and 17mm basis (external specification).
MOD projects will be designed on a 30mm basis (internal specification).



Technoeconomics of **manufacture**


1.1 LUM = lumber development


prescriptive CLT from commodity lumber (edgewise properties)




1.2 LAM = lamstock development

performance-based CLT from custom lamstock (flatwise properties)








1.3 LAM electronic grades (proprietary)



1.4 LAM sections





1.5 LAM strength and stiffness certifications


	1.8E-1575T
35x135 DF	
1216	1.8E LAM-6 (0.83")
MC12	0.50 SG 1575 Ft 2100 Fb


ELAM grading rules limit the percentage of the cross section allow for a combination of knots, knot holes, burls, distorted grain, an decay at the edges of the cross section. The actual size changes with graded width and can be expressed as a size for clarity with setting the grading machine.


Normalization with external lumber grades to internal lamstock categories is possible after transformation to lamstock in the factories. All incoming lumber is sorted and remediated to lamstock specifications without negating the external strength and stiffness grading.

	1.8E-1575T
35x135 DF	
1216	1.8E LAM-6 (0.83")
MC12	0.50 SG 1575 Ft 2100 Fb

	1.8E-1575T
35x180 DF	
1216	1.8E LAM-6 (1.17")
MC12	0.50 SG 1575 Ft 2100 Fb

	1.8E-1575T
35x135 DF	
1216	1.8E LAM-5 (1.17")
MC12	0.50 SG 1375 Ft 1950 Fb

	1.8E-1575T
35x180 DF	
1216	1.8E LAM-5 (1.25")
MC12	0.50 SG 1375 Ft 1950 Fb

	1.8E-1020T
35x135 DF	
1216	1.8E LAM-4 (1.25")
MC12	0.50 SG 1020 Ft 1650 Fb




	1.8E-1020T
35x180 DF	
1216	1.8E LAM-4 (1.75")
MC12	0.50 SG 1020 Ft 1650 Fb

TABLE 1.X

ASD Design Values^(a) for Laminations Used in CLT and GLT

Allowable Design Properties for Laminations Used in CLT								
LAM Grade		Laminations Used in Major and Minor Strength Directions (minimum properties allowed)				SG	f _{v,0.0.5} (psi)	f _{c,90.0.5} (psi)
		E (10 ⁹ psi)	f _t (psi)	f _b (psi)	f _c (psi)			
f _v = 0.96 x SG ÷ 40 f _{c,90} = 0.93 x SG ÷ 40								
2.1E-2050T	2.10	2050	2550	2037	0.36 0.38 0.40 0.42 0.44 0.46 0.48 0.50 0.52 0.54 0.56 0.58	ASTM D ⁶⁵⁷⁰⁻¹⁸ _a X ^{1.1}	ASTM D ⁶⁵⁷⁰⁻¹⁸ _a X ^{1.2}	
2.1E-1575T	2.10	1575	2100	1869				
2.0E-1925T	2.00	1925	2400	1981				
1.9E-1750T	1.90	1750	2250	1925				
1.8E-1575T	1.80	1575	2100	1869				
1.8E-1375T	1.80	1375	1950	1813				
1.8E-1020T	1.80	1020	1650	1701				
1.5E-1575T	1.50	1575	2100	1869				
1.5E-1375T	1.50	1375	1950	1813				
1.5E-1020T	1.50	1020	1650	1701				
1.5E-0750T	1.50	750	1250	1552				
1.5E-0500T	1.50	500	900	1421				
1.2E-1375T	1.20	1375	1950	1813				
1.2E-1020T	1.20	1020	1650	1701				
1.2E-0750T	1.20	750	1250	1552				
1.2E-0500T	1.20	500	900	1421				
1.2E-0350T	1.20	350	750	1365				
0.9E-0750T	0.90	750	1250	1552				
0.9E-0500T	0.90	500	900	1421				
0.9E-0350T	0.90	350	750	1365				






CLT characterization

out-of-plane BENDING strength and stiffness
out-of-plane SHEAR strength and stiffness
in-plane SHEAR strength and stiffness






CLT characterization

- out-of-plane BENDING strength and stiffness
- out-of-plane SHEAR strength and stiffness
- in-plane SHEAR strength and stiffness






CLT characterization



out-of-plane BENDING strength and stiffness
out-of-plane SHEAR strength and stiffness
in-plane SHEAR strength and stiffness




1.6 CLT strength and stiffness certifications



Like lamstock, stiffness and strength classes can be established for composite sections of CLT and GLT. This normalization is similar to prescriptive glulam grades in published standards and allows normalization of material performance parameters. Design values for each section and species combinations are clearly noted at the bottom of the grade stamp. The complexity of the multiple agency and standards pathways is captured in the overarching ICC-ES product report.





Strategic Intent: Add CLT production dedicated to modular.

- Existing CLT production serves **BID** project growth
- New CLT production serves **MOD** project growth

Technoeconomics of **value chains**


Key Takeaway: Modular (MOD) projects are a market expansion strategy to complement existing design-bid-build (BID) projects.


Strategic Intent: Increase CLT production from ~25k m³ to ~75k m³.

1. **PHASE 1 SHIFT** (2025) capitalizes existing primary manufacturing assets
 2. **PHASE 2 SHIFT** (2026) capitalizes proposed secondary manufacturing assets
- PNW market diffusion models by Beyreuther, Ganguly 2016-2020 model

Technoeconomics of **scale**


Key Takeaway: MOD projects on 30mm basis complement BID projects on 35mm basis.





Technoeconomics of **manufacture**

Strategic Intent: Increase utilization in CLT production processes




Technoeconomics of **manufacture**

Strategic Intent: Increase utilization in CLT production processes



⚠ DANGER


- 1. Do not touch the moving parts.
- 2. Do not touch the moving parts.
- 3. Do not touch the moving parts.
- 4. Do not touch the moving parts.
- 5. Do not touch the moving parts.
- 6. Do not touch the moving parts.
- 7. Do not touch the moving parts.
- 8. Do not touch the moving parts.
- 9. Do not touch the moving parts.
- 10. Do not touch the moving parts.



Technoeconomics of **manufacture**

Strategic Intent: Increase utilization in CLT production processes

1m x 1m x 1m = (1) timber**blok**




(1) 18.3m x 3.6m x CLT3_090mm billet approximately = (6) timber**bloks**


Technoeconomics of **manufacture**

Strategic Intent: Increase utilization in CLT production processes

SUPPLY CHAIN 0
(baseline 2011)



SUPPLY CHAIN 3
(proposed 2025)



Key Takeaway: Modular (MOD) projects are a market expansion strategy to complement existing design-bid-build (BID) projects.



POST and BEAM

GLT columns, beams, purlins

CLT one-way floor plates



POST and BEAM

GLT columns, beams, purlins


CLT one-way floor composite ribbed plates



POST and BEAM

GLT columns, beams, purlins

CLT one-way floor plates



BEARING WALL

CLT walls

CLT floor plates




POST and PANEL

GLT columns

CLT floor plates (two-way)

CFS non-structural infill




POST and BEAM

STEEL columns, beams

CLT floor plates

CFS non-structural infill



BEARING WALL

CFS structural walls

CLT floor plates



POST and BEAM

GLT columns, beams

CLT floor plates

CFS non-structural infill

MOD ASSEMBLIES

CLT floor plates
CLT framing components
CLT non-structural infill






MOD ASSEMBLIES

CLT floor plates
CLT framing components
CLT non-structural infill




MOD ASSEMBLIES

CLT floor plates
CLT framing components
CLT non-structural infill



WA
local ecologies and economies focus
state political boundary




WA, OR, ID, MT
supply chain focus
regional resource boundary

WA, OR, CA, (BC)
market focus
regional policy boundary




US
codes and standards focus
federal political boundary





Technoeconomics of **regions**

Strategic Intent: drive codes and policy at regional scales

Mass Timber Code and Policy Development



LAM – CLT – MOD



[illegible]

**GROUP R
TYPE VA OVER IWB
RESIDENTIAL**

70'-0"

GROUP R1
GROUP R2
GROUP R3
GROUP R4
GROUP R5
GROUP R6
2-PIECE HORIZONTAL ASSEMBLY
GROUP R7
GROUP R8


30'-0"
TYPE VA



30'-0"
TYPE IWB

70'-0"

TYPE VA


- 5-STORIES MAX WITH STAIR PRESSURIZATION PER 506.4.1
- 70 FT MAX HEIGHT ABOVE GRADE PLANE
- 1-HOUR RATED STRUCTURE







Technoeconomics of **manufacture**




Technoeconomics of **manufacture**

'Boolean' methods

Tectonic detailing derived from linear scripting of processes.

(image: Beyreuther, 2022)




Technoeconomics of **manufacture**

'Boolean' methods

Tectonic detailing derived from linear scripting of processes.

(image: Beyreuther, 2022)



Technoeconomics of **manufacture**


MOD volumetric assemblies



MOD assemblies


European precedents demonstrate durable assemblies and advanced manufacturing processes integrating 'light' mass timber components (Renggli AG, Schötz, Switzerland)






MOD hybrid framing

Targeting prefabrication assembly lines, MOD framing components with both cross-laminated timber (CLT) and glued-laminated timber (GLT) material offers custom solutions for assembly lines.






MOD hybrid framing



Targeting prefabrication assembly lines, MOD framing components with both cross-laminated timber (CLT) and glued-laminated timber (GLT) material offers custom solutions for assembly lines.

Grades: 1.2E, 1.5E

Layups: CLT3-090, CLT5-150, GLT3-090, GLT5-150

Species: DF, GF, WH, SPF





MOD hybrid framing

Grades: 1.2E, 1.5E

Layups: CLT3-090, CLT5-150, GLT3-090, GLT5-150

Species: DF, GF, WH, SPF

MOD seismic detailing

Assemblies with mass timber components require new ways of detailing to demonstrate seismic equivalency with existing, mature systems (e.g. light wood frame).




MOD seismic detailing

Assemblies with mass timber components require new ways of detailing to demonstrate seismic equivalency with existing, mature systems (e.g. light wood frame).





MOD seismic detailing

Assemblies with mass timber components require new ways of detailing to demonstrate seismic equivalency with existing, mature systems (e.g. light wood frame).



MOD seismic certification



Assemblies with mass timber components require new ways of detailing to demonstrate seismic equivalency with existing, mature systems (e.g. light wood frame).



System	Standards	Seismic Design Coefficients			IBC Construction Type
		R	Ω_0	C _d	
Ordinary CLT SW	SDPWS 2021	1.5	2.5	1.5	Type III, IV, V
SDPWS Appendix B CLT SW	SDPWS 2021 ASCE 7-22	3 (2:1) 4 (4:1)	3 3	3 4	Type III, IV, V
Oregon Alternative CLT SW	Oregon SAM 15-01	2	2.5	2	Type III, IV, V
STRIAE LFW equivalency CLT SW	ASCE 7-22 ASTM D7989-21	6.5	3	4	Type III, V

MOD seismic certification

Assemblies with mass timber components require new ways of detailing to demonstrate seismic equivalency with existing, mature systems (e.g. light wood frame).



MOD volumetric assemblies

Grades: 1.2E, 1.5E, 1.8E, 1.4V

Layups: CLT3-090, CLT5-150,
GLT3-090

Species: SPF, DF, GF, WH




MOD volumetric assemblies

Grades: 1.2E, 1.5E, 1.8E

Layups: CLT3-090, CLT5-150
GLT3-090

Species: GF



Alpine Housing (1.2+ AMI)

(image: Beyreuther, 2024)
AMI = Area Mean Income

MOD volumetric assemblies

Grades: 1.2E, 1.5E, 1.8E

Layups: CLT3-090, CLT5-150
GLT3-090

Species: GF



Alpine Housing (1.2+ AMI)

(image: Beyreuther, 2024)
AMI = Area Mean Income



Scaling Offsite and Volumetric Modular

Todd Beyreuther PE

Head of Platform Development, Earth Force Build

This concludes The American Institute of Architects Continuing Education Systems Course.

MODULAR MASS TIMBER

Bringing construction into the
digital / robotic era

**INTEGRATED
DESIGN CUBED**
MODULAR MASS TIMBER

P e t e r R o s e + P a r t n e r s | NKBAK | Kaufmann Bausysteme

Disclaimer: This presentation was developed by a third party and is not funded by WoodWorks or the Softwood Lumber Board.

MODULAR MASS TIMBER KEY ELEMENTS

Mass Timber



MODULAR MASS TIMBER KEY ELEMENTS

Mass Timber – Robotically Fabricated



MODULAR MASS TIMBER KEY ELEMENTS

Mass Timber Modules



MODULAR MASS TIMBER KEY ELEMENTS

Mass Timber Modules



MODULAR MASS TIMBER KEY ELEMENTS

Modular Mass Timber Buildings



MODULAR MASS TIMBER

An Integrated Team

IDCUBED



Peter Rose, AIA, FRAIC
IDCUBED Co-Founder

Peter Rose + Partners
Founding Principal

Harvard GSD
Professor



Andreas Krawczyk
IDCUBED Co-Founder

NKBAK
Founding Principal



Christian Kaufmann
IDCUBED Partner

Kaufmann Bausysteme (KBS)
Founding Principal



Stani Iordanova
IDCUBED Senior Director

Peter Rose + Partners
Principal



Christopher Flass
IDCUBED Project Director

Peter Rose + Partners
Principal



Justin Cook
IDCUBED Co-founder

RISD Center for Complexity
Founding Director

FABRICATORS



Todd Thesing
Fabrication Partner

Highline Partners
Co-Founder




Rob McRae
Fabrication Partner

Highline Partners
Co-Founder

An integrated team of highly skilled architects and fabricators, *in constant communication*, designing and directing every aspect of the process.

MODULAR MASS TIMBER KEY ELEMENTS

Software




Supply chain and local module assembly managed remotely by our software.

MODULAR MASS TIMBER PROJECTS



**Exceptional buildings
for users and owners.**

MODULAR MASS TIMBER PROJECTS



Every project:
on time, on budget.

MODULAR MASS TIMBER PROJECTS



**A wide range of programs,
scales, and contexts.**

MODULAR MASS TIMBER PROCESS (3 STAGES)

Stage 1. Integrated Design Of Everything

Buildings

Modules

Timber and Other Components

Supply Chain

Assembly Process




KEY OBJECTIVES:

very good buildings

modules - very easy to assemble


buildings - very easy to assemble

constant improvement




MODULAR MASS TIMBER PROCESS (3 STAGES)

Stage 1: Integrated Design of Everything - Buildings



MODULAR MASS TIMBER PROCESS (3 STAGES)

Stage 1: Integrated Design of Everything: Modules



MODULE C : Bedroom + Pantry/Mudroom

FLOOR/CEILING
3 lam / 0.3' thick

LONG WALLS
3 lam / 0.3' thick

END WALLS
4 lam / 0.4' thick

INTERIOR WALLS
3 lam / 0.3' thick

001

011

012

021

022

031

034

25' - 10"

7' - 4"

x 2

25' - 10"

4' - 0"

8' - 0"

10' - 6"

25' - 10"

8' - 0"

10' - 6"

8' - 0"

10' - 6"

7' - 4"

4' - 0"

3' - 0"

2' - 4"

6' - 10"

9' - 6"

8' - 6"

9' - 6"

3.2

4.6

1.9


1.29

total volume	11.02 m ³
total components	7

Modules designed to meet the specific needs of each project. A wide range of sizes, configurations, shapes is possible.

MODULAR MASS TIMBER PROCESS (3 STAGES)

Stage 1: Integrated Design of Everything: Timber Components



Robotically Fabricated

By Multiple Suppliers

MODULAR MASS TIMBER PROCESS (3 STAGES)

Stage 1. INTEGRATED DESIGN OF EVERYTHING

Stage 2. MODULE ASSEMBLY

Directed – on tablets –
by proprietary software.

Supply chain also
managed by proprietary
software.

Supply chain and module
assembly are **managed
remotely**.



MODULAR MASS TIMBER PROCESS (3 STAGES)

Stage 2: Module Assembly: Software-directed



Instructions For Every Task

On A Tablet

At Every Module Station

MODULAR MASS TIMBER PROCESS (3 STAGES)

Stage 2: Module Assembly



Assembly Hall, not a Factory Rented, not Owned A Crane, no Robots

MODULAR MASS TIMBER PROCESS (3 STAGES)

Stage 2: Module Assembly




Worker Friendly

Builder Friendly

MODULAR MASS TIMBER PROCESS (3 STAGES)

Stage 2: Module Assembly:
Software-directed, remotely

KBS Headquarters
Reuthe, Austria



Assembly Hall 2
Rostock



Assembly Hall 1
Berlin



Module Assembly

Remotely Managed

From KBS HQ

MODULAR MASS TIMBER PROCESS (3 STAGES)

Stage 2: Module Assembly:
Software-directed, remotely



KBS Headquarters
Reuthe, Austria



IDCUBED and Assembly Halls
Anywhere in North America

MODULAR MASS TIMBER PROCESS (3 STAGES)

Stage 1. INTEGRATED DESIGN OF EVERYTHING

Stage 2. MODULE ASSEMBLY


Stage 3. BUILDING ASSEMBLY

Sitework

Setting of modules

Facade / Roof


Hook-ups



MODULAR MASS TIMBER IN NORTH AMERICA


Knight Building, Big Sky, MT

The First Large-Scale
Modular Mass Timber
Building in the U.S.



MODULAR MASS TIMBER IN NORTH AMERICA

Knight Building, Big Sky, MT



120 modules

Set at a max rate of 20 per day

96 occupants

12 suites


8 bedrooms per suite

MODULAR MASS TIMBER IN NORTH AMERICA

Knight Building, Big Sky, MT

BEDROOM

LIVING ROOM



MODULAR MASS TIMBER IN NORTH AMERICA

Knight Building, Big Sky, MT



Workforce housing for 95 employees

31,000 GSF

11 months on-site construction

On time

Under budget

Sustainable, all electric, solar array

Stores 1,200 tons of carbon

MODULAR MASS TIMBER KEY ELEMENTS

Mass Timber



GLT Glue-laminated timber

CLT Cross-laminated timber

**A game-changing
innovative material.**

Precise, strong, beautiful.

**CLT panels available in
very large sizes.**

(up to 12' x 60' x 11")

MODULAR MASS TIMBER KEY ELEMENTS

Mass Timber Components




Components fabricated robotically with extreme precision to our specifications by others.

Available from a wide range of mass timber suppliers in North America and Europe.





MODULAR MASS TIMBER KEY ELEMENTS

Mass Timber Modules



- Modules designed strategically with the goals of:
1. **Easy and quick assembly** by small teams of relatively low-skilled laborers in local assembly halls.
 2. **Easy and quick setting** on site
 3. **Exceptional buildings**




**INTEGRATED
DESIGN CUBED**
MODULAR MASS TIMBER



Resilient Homes

**Disclaimer: this presentation was developed by a third party and is not funded by WoodWorks or the Softwood Lumber Board*

Manual Design



Paper Processes

High Capital Cost



550,000+ Skilled Worker Shortage

Long Tail Problem

7 Climate Zones
50 States
~30k Zoning Jurisdictions



Pipeline Adaptability Challenge




Production Uncertainty

Construction needs a paradigm shift



No Volumetric Approach



Hardware-Defined Rigid Systems

Reframe Systems

3 years old, founding team from Kiva Systems and Amazon Robotics.

Delivering homes to paying customers. Vertically integrated. 40X production growth in 2025




Microfactory #1 operational in Andover, MA

Microfactory #2 in Los Angeles EOY 2026


Reframe is building climate-resilient homes using robotics, algorithms, and a microfactory network. We're turning construction into computation to unlock housing abundance.



We're reframing construction into a software and AI problem





Augmented Workcells
Supercharges Apprentice Builders




Low-Cost Flexible Robots
Physical World API

Highly detailed parametric CAD



Work instructions drive shop floor efficiency



1 Triple Decker




24 Modules +
6 Roof Cassettes

X

~200 Work Instructions/Module
(100 Annotated Views/Module)

= ~3500 Work Instructions (800 unique annotated views) per project




Reframe Robotic Paneling




50x smaller, 25x cheaper

	Modular 2.0	Modular 3.0 (Reframe Systems)
CAPEX	High (>\$5M)	Low (\$200k)
Installation Time	800 days	100 days
Flexibility	Very Low	Very High
Scaling/Utilization	None/Low	Yes/High
Throughput	150 linear ft/hr	36 linear ft/hr
Footprint	26,000 sqft	500 sqft
Min Factory Footprint	200k sqft	20k sqft

Modular 2.0



From #2 Lumber - High performance buildings



Software is material agnostic

Delivered our first climate-resilient home in 48 days



**2.5X
Faster**

48 days vs. 120 days
Foundation to Substantial
Competition

**20%
Tighter**

0.47ACH50 vs.
0.6ACH50

**85%
Less Carbon**

Compared to non-Passive
two-story home



Reframe Living

PORTFOLIO





This concludes The American Institute of Architects
Continuing Education Systems Course.